



CITY OF BATON ROUGE / PARISH OF EAST BATON ROUGE
DEPARTMENT OF DEVELOPMENT
SUBDIVISION ENGINEERING / FLOODPLAIN MANAGEMENT

AS-BUILT PLAN REQUIREMENTS

AS-BUILTS shall show ALL improvements, **BOTH PUBLIC AND PRIVATE**

Gravity Sewer Pipe Table

- Pipe Designation
- Size
- Length
- Slope
- Material (PVC, Ductile Iron, HDPE, other)
- Public or Private

Sewer Manhole Table

- MH Designation
- Size (Diameter)
- Type (Drop, or not)
- Top Elevation
- Invert Elevation
- Northing & Easting
- Public or Private
- Surface Type Surrounding

Reference C-P MH-ID# when connection to existing MH.

Include Northing and Easting for center of Pump Station Wet Well.

Drainage Structure Table

- Type
- C-P Standard #
- Grate (From C-P Std)
- Top Elevation
- Invert Elevation
- Northing & Easting
- Public or Private
- Surface Type Surrounding

Drainage Pipe Table

- Size (width & height)
- Length
- Slope
- Material/Type (Use Standard List)
- Public or Private

For arch pipe provide actual width and height, in addition to the equivalent sizing.

Drainage Pipe Material/Type Standard List

- CMP (Corrugated Metal Pipe, includes BCCMP)
- RCP (Reinforced Concrete Pipe)
- PVC (Including A2000)
- HDPE
- Box Culvert
- Other